

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION Q9E 1/4

SEC. 11 TWP. 18 RGE. 16W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Hazelbent

Operator Wentworth K. Kohn Address Box # 552 - Tulsa Okla

Field \_\_\_\_\_ County Nowata

Total Depth 3618 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 418 ft - Circulated with cement  
12 1/2 - 1006 ft - We found the 15 1/2 & the 12 1/2 cement together  
7" casing set at 3495 ft - cemented with 90 sacks cement.  
Plugged back to 3460 ft with pack - Cement from 3460 ft to 3420 ft  
27 sacks cement - Shot off & pulled 1700 ft of 7" casing -  
Well flowing because of salt water - Pumped in  
plug & 600 sacks of cement - Filling the 12 1/2 casing -  
from 800 ft up to the surface with cement.

To deep - 9-8-50 - I cut off the 15 1/2 & the 12 1/2 at the bottom  
of the collar - Found cement that O.K. labeled plate on top of 12 1/2 &  
15 1/2 cas - 7 -

9-11-50  
SEP 11 1950

E. C. Strong, Jr.  
District Conservation Agent

Date 9-8-50

**PLUGGING**  
FILE SEC 11 T 18 R 16W  
BOOK PAGE 27 LINE 10

X