

15-165-20460-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1974
5-2-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Aspen Drilling Company

Complete Address P. O. Box 783, Great Bend, Kansas 67530

Lease Name Butherus Well No. 1

Location N/2 N/2 SW Sec. 11 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3045'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pawnee Drilling Co., Inc.

Address Great Bend, Kansas License No. 633

Operation Completed: Hour 3:45 P Day 30 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3045' 8 5/8 csg set at 1034' cwc 450 sk.

5 1/2 csg set at 3040' Top of cement 1593'

5 1/2 csg PBTD 2330' with perf. (1889-1899'

Set 5 1/2 wood plug at 1800' -poured 50' sand -dumped 5 sk cement W/dump bailer.

Shutoff and recovered 1530' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 350' -set rock & sand bridge (350-385)

Filled with readymix cement from 325' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Mearns
Well Plugging Supervisor

INVOICED

DATE 5/2/74

INV. NO. 9034-W