

15-165-01806-0000

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 82-11 Location: N $\frac{1}{2}$ S $\frac{1}{2}$ SW

County: Rush Sec. 25 Twp. 18 Rge. 16 (E) (W)

Name of Field or Pool: _____ Total Depth: 3566

I have this date completed supervision of plugging of:

Well No. 1 Lease Hergert

Operator's Full Name Clark Knight Oil Co Drilg. Co., Inc.

Complete Address: Box 162 Great Bend, Kans

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 10AM Day 18 Month 2 Year 58

The above well was plugged as follows:

8 5/8" at 985' circulated with cement - 5 1/2" 3555' with 50 sax cement.
Filled with sand to 3540', set 4 sax cement with dump bailer, pulled
3225' 5 1/2" - mudded hole with heavy chunk mud to 450', set bridge and
25 sax cement, heavy mud to 200', set bridge and 25 sax cement, heavy
mud to 35', set rock and 10 sax cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed:
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
FEB 24 1958
REGISTRATION DIVISION
Wichita, Kansas

Reviewed: J. Lewis Beck
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks:

PLUGGING
FILE NO. 25 T 18 R 16 W
BOOK PAGE 82 LINE 11