

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1959
12-30-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush

Location: CSL SE 1/4 Sec. 25 Twp. 18 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3598

I have this date completed supervision of plugging of:

Lease Name: Geisick Well No. 3

Operator's Full Name: Northern Natural Gas Co

Complete Address: Great Bend, Kans

Plugging Contractor: ~~NAME~~ Forbes Casing Pulling Co & Globe Cementing Co

Address: _____ License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 23 Month 12 Year 59

The above well was plugged as follows:

13" 270' circulated with cement - 8 5/8" 992' circulated with cement -
5 1/2" 3598' with 100 sax cement - run tubing in hole and cemented to 2900'
through 2" - pulled tubing and 2010' 5 1/2" - rerun tubing and mudded hole
2900' to 2100' - filled hole with cement 20% Diocel from 2100' to 0' through
2" tubing - 402 Sax cement and 102 sax Diocel.
Mudding and cementing by Globe Cementing Co.

Signed: *E. Lewis*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 687-W