

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

*Handwritten mark*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 100-1 Location: CW $\frac{1}{2}$  W $\frac{1}{2}$  SW

County: Rush Sec. 25 Twp. 18 Rge. 16 (E) (W)

Name of Field or Pool: \_\_\_\_\_ Total Depth: 3554

I have this date completed supervision of plugging of:

Well No. B-1 Lease Hergert "0"

Operator's Full Name T. L. Nutt

Complete Address: Box 407 Ellinwood, Kans

Plugging Contractor: Glenn & Smith

Address: \_\_\_\_\_ License No. 596

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 8Am Day 22 Month 5 Year 58

The above well was plugged as follows:

15" at 203' circulated with cement - 10 3/4" 976' circulated with cement,  
7" 3529' with 200 sax cement behind.

Filled with sand to 3520', set 5 sax cement with dump bailer, pulled  
2842' 7" - filled with heavy chunk mud to 300', set 30 sax cement, heavy  
chunk mud to 40', set rock and 15 sax cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edson Leedy*  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

\_\_\_\_\_  
6-7-58

Reviewed: *J. Lewis Beck* Signed: \_\_\_\_\_  
Field Supervisor Well Plugging Supervisor

Remarks:

PLUGGING  
20 25 18 16w  
PAGE 100 LINE 1