

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-077-20332-0000

LEASE NAME Bishop

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER #1

SPOT LOCATION 150 E/SW NE NE

SEC. 19 TWP. 31S RGE. 6 (E) OR (W)

COUNTY Harper

DATE WELL COMPLETED 10/29/75

PLUGGING COMMENCED 10/11/84

PLUGGING COMPLETED 10/29/84

LEASE OPERATOR Hummon Corp.

ADDRESS 400 One Man Place, Wichita, KS 67202

PHONE # ( 316 ) 263-8521 OPERATORS LICENSE NO. 5050

CHARACTER OF WELL Gas  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita, KS

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 4372

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION.	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	261	None
				5 1/2	4371	2200

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plug back 4366

Sand from 4366 to 4300, 5sx cement from 4300 to 4270

Sun pump in 3sx bulls, 6sx jell, 100sx cement  
Comm. 2% C.C.

Max 700 - Shut in 500 3:30

Elmo Morgenstern on location

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Clarke Corp. LICENSE No. 5105

ADDRESS Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, SS.

Elmo Morgenstern (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

CAREN J. McCULLOUGH  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6/29/87

(SIGNATURE) Elmo Morgenstern  
(ADDRESS) \_\_\_\_\_

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6 DAY OF Nov, 1984

Caren J. McCullough  
NOTARY PUBLIC

MY COMMISSION EXPIRES: June 29, 1987

RECEIVED FORM CP-4  
STATE CORPORATION COMMISSION REVISION 06-83

NOV 08 1984  
11-8-84  
CONSERVATION DIVISION  
Wichita, Kansas

15-077-10332 0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Bishop #1  
Sec 17-31S-6W  
Harper County Kansas

Commenced: 10-16-75

Completed: 10-29-75

OPERATOR: HUMMON OIL CO.

Depth		Formation	Remarks
From	to		
0	25	Sand	
25	264	Redbed	
264	1070	Redbed-Shale	Ran 6 jts of used 8 5/8" csg set @ 261' Cemented w/ 225 sks Common 3% CC
1070	1470	Shale-Shells	PD @ 5:15 a.m. 10-17-75
1470	1665	Lime-Shale	
1665	1977	Shale-Lime	
1977	2120	Lime-Shale	
2120	2335	Shale-Lime	
2335	2530	Lime-Shale	
2530	2900	Lime	
2900	3075	Lime-Shale	Ran 142 jts of New 5 1/2" csg set @ 4371' Cemented w/75 sks 60/40 Posmix
3075	3220	Lime	15% Salt - 6# Gilsonite
3220	3625	Lime-Shale	PD @ 3:00 a.m. 10-29-75
3625	3675	Shale	
3675	3770	Lime-Shale	
3770	3817	Shale-Lime	
3817	4372	Lime	
	4372 TD		

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled Sec 17-31S-6W, Harper County Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
JAMES S. SUTTON II

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Before me, the undersigned, A Notary Public within and for said County and State, on this 6th day of December, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I HAVE hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

RECEIVED  
STATE COMMISSION  
OCT 05 1984  
10-5-84  
Wichita, Kansas