

15-077-00151-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Harper County, Sec. 11 Twp. 31 Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Beardmore Drilling Company
Lease Name Williams Well No. 1
Office Address 603 Petroleum Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 21 19 54
Application for plugging filed March 21 19 54
Application for plugging approved March 21 19 54
Plugging commenced March 21 19 54
Plugging completed March 21 19 54
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 4493 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	70			
Sand		70	100			
Red Rock & Shale		100	175	8-5/8"	175'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

- 175' to 4493' - Heavy Mud
- 175' - Wood Plug
- 130' to 175' - 15 Sacks Cement
- 35' to 130' - Heavy Mud
- 35' - Wood Plug
- 0' to 35' - 5 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company
Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.

I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of March, 1954

Leonard P. Tolle Notary Public.

My commission expires January 28, 1956

RECEIVED
MAR 30 1954
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 11 T 31 R 8W
BOOK PAGE 22 LINE 33

WILLIAMS NO. 1

SE SW SW
Section 11-31S-8W
Harper County, Kansas

Drilled for: Beardmore and O.A. Sutton
Drilled by: Beardmore Drilling Company

Casing Record:

8-5/8" 175⁺w/110 Sacks

Drilling Commenced: March 9, 1954
Drilling Completed: March 21, 1954

Elevation: DF 1634

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Sand	35
Clay	70
Sand	100
Red Rock - Shale	175
Shale - Shells	1250
Lime - Shale	1505
Shale - Lime	1785
Lime - Shale	1950
Shale - Lime	2640
Lime - Shale	3270
Shale - Lime	3380
Lime - Shale	4010
Lime	4155
Lime - Shale	4425
Lime	4493 T. D.

D & A

TOPS:

Topeka	2989
Heebner	3380
Kansas City	3905
Mississippi	4424

STATE OF KANSAS

ss

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Alfred Beardmore

Subscribed and sworn to before me this 29th day of March, 1954.

Leonard P. Tolle
NOTARY PUBLIC

My Commission Expires:
January 28, 1956

