

15-077-01005-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper County, Sec. 28 Twp. 31S Rge. (E) 5 (W)

Location as "NE/CNW&SW&" or footage from lines SW SW SE
Lease Owner Natural Gas and Oil Company
Lease Name HEIBERT Well No. 1
Office Address P. O. Box 105, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 3 1958
Application for plugging filed September 3 1958
Application for plugging approved September 3 1958
Plugging commenced September 3 1958
Plugging completed September 3 1958
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4673 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	351	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud total depth to 300 feet
Plug, 1/2 sack hulls, 20 sacks cement
Mud to 35 feet
Plug, 1/2 sack hulls, 10 sacks cement

TMB
1-25-13
already listed

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. B. Steele, Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P. O. Box 105, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 1958

Richard R. Beach Notary Public.

My commission expires July 27, 1959

PLUGGING
FILE SEC. 28 T. 31 R. 5W
BOOK PAGE 120 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1958
9-6-58
CONSERVATION DIVISION
Wichita, Kansas

D R I L L E R S L O G

#1 Heibert

CASING RECORD: 11 Jts. or 351' of 8-5/8" surface casing	COMPANY: Natural Gas & Oil Co.	DESCRIPTION: SW SW SE Section 28-31S-5W Harper County, Kansas
TOTAL DEPTH: 4673'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 1335' RB 1332' DF
	COMMENCED: August 14, 1958	
	COMPLETED: September 3, 1958	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	15	Ran 11 Jts. or 351' of 8-5/8" surface casing; cemented with 250 sacks of cement.
Sand	15	25	
Shale (Red)	25	280	2% Gel & 2% C. C..
Shale	280	440	<u>DST #1</u> Packer set @ 3709'. Total Depth @ 3718'; tool open 1 hr. good blow through-
Shale & Shells	440	870	out. Recovered 600' gas, 60' gas & Oil cut
Anhydrite	870	890	mud, 60' gas & Oil cut water. BHP 1210 lbs.
Shale & Shells	890	1100	IFP 32 lbs. FFP 60 lbs. in 20 minutes.
Lime & Shale	1100	2280	<u>DST #2</u> Packer set @ 3740'. Total Depth @ 3755'; tool open 1 hr. strong blow through-
Shale	2280	2420	out test. Recovered 115' gas cut slightly
Lime & Shale	2420	3630	oil cut watery mud, 180' gas cut muddy
Lime	3630	3995	water. BHP 1495 lbs. IFP 53 lbs. FFP
Lime & Shale	3995	4234	145 lbs. in 20 minutes.
Chert & Lime	4234	4462	<u>DST #3</u> Packer set @ 4649'. Total Depth @ 4653'; tool open 1 hr. weak blow through-
Mississippi	4462	4500	out test. Recovered 5' mud. BHP 1410 lbs.
Mississippi Lime	4500	4529	FFP 65 lbs. IFP 18 lbs. in 20 minutes.
Shale	4529	4547	<u>DST #4</u> Packer set @ 4653'. Total Depth @ 4663'; tool open 1 hr. very weak blow,
Lime	4547	4559	recovered 10' mud. BHP 1280 lbs. FFP 35
Shale & Lime	4559	4644	lbs. IFP 25 lbs. in 20 minutes.
Shale	4644	4649	<u>DST #5</u> Total Depth @ 4673; tool open 1 hr.
Sand	4649	4673	Recovered 505' muddy water. BHP 1790 lbs.
			FFP 270 lbs. IFP 130 lbs. in 20 minutes.

TOTAL DEPTH 4673'

STATE OF KANSAS)
) ss:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Tres.

Subscribed and sworn to before me this 4th day of September, 1958.

Elaine H. Taylor
Elaine H. Taylor, Notary Public
NOTARY PUBLIC
REGISTRATION COMMISSION

My Commission Expires:

December 14, 1961

PLUGGING
FILE SEC. 28 T 31 R 5W
BOOK PAGE 120 LINE 12

SEP 10 1958
9-10-58
CONSERVATION DIVISION
Wichita, Kansas

SEP 9 - 1958