

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 28 Twp. 31S Rge. 5 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner Walters Drilling Company
Lease Name Gerber Well No. 1
Office Address 400 Insurance Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 10-15-68 19
Application for plugging approved 10-16-68 19
Plugging commenced 10-20-68 19
Plugging completed 10-22-68 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Depth to top Bottom Total Depth of Well 1609 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	328	None
				5 1/2	None 4666'	3190

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3700'. Dumped 5 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3205'. gas blew in. Pulling pipe.

Pulling pipe. Plugging well. Bailed to 250' rock bridge. Dumped 25 sacks of cement. Mud hole and rock bridge. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of October, 1968

My commission expires May 27, 1969 Notary Public.

W E L L L O G
 Gerber # 1
 SW SE SW 28-31S-5W
Harper County, Kansas

0 - 70	Surface clay and sand	<u>Elevation</u>	<u>1332 DF</u>
70 - 180	Shale and shells		
180 - 321	Red bed and shale		
321 - 900	Shale and shells	<u>Tops of Formation:</u>	
900 - 1080	Lime		
1080 - 1260	Lime and shale	Topeka	2582
1260 - 1735	Lime	Heebner	2973
1735 - 1815	Lime and shale	Lansing	3549
1815 - 1900	Lime	B. Kansas City	3789
1900 - 2795	Lime and shale	Marmaton	3866
2795 - 2885	Lime	Mississippi	4169
2885 - 3590	Lime and shale	Kinderhook	4526
3590 - 3825	Lime	Simpson	4629
3825 - 4196	Shale and lime	T. D.	4667
4196 - 4329	Cherty Lime		
4329 - 4370	Lime		
4370 - 4386	Lime and chert		
4386 - 4503	Lime		
4503 - 4532	Lime and chert		
4532 - 4572	Lime and shale		
4572 - 4638	Shale		
4638 - 4651	Simpson sand and shale		
4651 - 4667	Simpson sand		
4667	T.D.		

STATE OF KANSAS

COUNTY OF BARTON ss

T. D. Sweetman, President of Dutch Drilling Company, Inc.,
 being first duly sworn on oath says: That I have knowledge of the facts,
 statements and matters herein contained and the log of the above described
 well as filed and that the same are true and correct.

T. D. Sweetman
 T. D. Sweetman

Subscribed and sworn before me this 25th day of September, 1957.

Virgil E. Belford, Jr.
 Virgil E. Belford, Jr.
 Notary Public, Barton County

My Commission expires April 27, 1961.

RECEIVED
 STATE CORPORATION COMMISSION
 16-16-68
 OCT 16 1968
 CONSERVATION DIVISION
 Wichita, Kansas