

15-077-30005-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec 1 Twp 31S Rge 7W (6) (W)



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines 6 NE/4 NW/4
Lease Owner National Cooperativer Refinery Association
Lease Name JOSLIN Well No. 1
Office Address 1417 Wichita Plaza Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 29 19 65
Application for plugging filed May 3 19 65
Application for plugging approved May 3 19 65
Plugging commenced April 29 19 65
Plugging completed April 29 19 65
Reason for abandonment of well or producing formation Dry Hole-No Commercial
Production

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	236'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 225 feet. Set plug at 225 feet, and cemented with 25 sacks of cement through drill pipe. Mudded to 40 feet. Set solid bridge and capped with 10 sacks of cement. Filled on up to base of casing.

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1965
5-13-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears C. R. Sears

1417 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 65

My commission expires November 26, 1968

NELL McCOMB

Notary Public.

ROTARY DRILLING LOG

OPERATOR: National Cooperative
Refinery Association
No. 1 JOSLIN
C NE NW Section 1-31S-7W
Harper County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.

COMMENCED: 4-16-65
COMPLETED: 4-29-65

REMARKS: Set 236' of 8-5/8"
surface casing with
175 sacks cement.

FORMATIONS:

Red Bed	870'
Shale & Shells	1200'
Anhydrite	1208'
Shale & Lime	1525'
Lime & Shale	2140'
Shale & Lime	3190'
Lime & Shale	3455'
Shale & Lime	3523'
Sand	3650'
Lime & Shale	3805'
Lime	4150'
Lime & Shale	4210'
Lime	4265'
Lime & Shale	4335'
Miss. Chert	4345'
Lime	4445'
Chert	4540'
Lime & Chert	4594'
Shale	4597'
Shale & Lime	4720'
Shale	4730'
Sand	4745'
Rotary Total Depth (D&A)	4745'

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1965
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the
State of Kansas, County of Sedgwick, this 3rd day of May, 1965.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public