

15-077-00017-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper County, Sec. 20 Twp. 31 Rge. 3 (E) W (W)

Location as "NE/CNW/SE" or footage from lines C N/2 SE SE
Lease Owner Rock Island Oil & Refining Co., Inc.
Lease Name Bear Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-15-60 _____ 19____
Plugging completed 8-19-60 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	None
				5-1/2"	4375'	3360'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4380' and found it clear.
Sanded hole to 4365' and dumped 5 sacks of cement with dump bailer. Pulled 5' casing. Checked fluid at 265', mudded to 220', set 10' rock bridge to 210' and ran 20 sacks of cement. Mudded to 40' set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1960
9-16-60
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knights Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1960

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



20-31-8W

15-077-60017-0000
NW/4 SE/4 NE/4
20-31-8
Harper County, Kansas
Casing: 223' of 8 5/8"
4374' of 5 1/2"

Phil Bear #1
Owner: Koch Oil Corp, Inc.
Contractor: Earl P. Wakefield
Comm: 2/12/55 Comp: 3/4/55

Elevation 1579 D. T.

Surface	238
Red Bed	810
Shale & Shells	1810
Lime	1820
Shale & Lime	2210
Shale & Shells	2435
Shale & Lime	3085
Sandy Lime & Shale	3312
Lime & Shale	3480
Shale, Sand & Lime	3601
Lime & Shale	3908
Lime	4160
Lime & Shale	4273
Lime & Sand	4325
Lime & Shale	4380
Total Rotary Depth	4380

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Phil Bear #1 well located NW/4 SE/4 NE/4, 20-31-8, Harper County, Kansas.

F. S. Barker

Sworn and subscribed before me this 9th day of March, 1955.

[Signature]
Notary Public

My commission expires July 26, 1958.

RECEIVED
STATE CORPORATION DIVISION
SEP 16 1958
9-16-60
CONSERVATION DIVISION
Wichita, Kansas