


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 30 Twp. 31S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Turley Oil Company
Lease Name Keller Well No. 1
Office Address 901 Office Park Plaza Bldg., Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-3-65 19
Application for plugging filed 10-3-65 19
Application for plugging approved 10-3-65 19
Plugging commenced 10-3-65 19
Plugging completed 10-3-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4715 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	216'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 215', plug, 1/2 sk. hulls, 25 sacks cement
Mud to 40', plug, 10 sks. cement, 2 sks. in rathole

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1965
10-7-65
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1965

My commission expires April 1, 1967

Notary Public.

DRILLER'S LOG

COMPANY: Turley Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: KELLER #1
 LOCATION: C SW SW Sec. 30-31S-6W
 HARPER COUNTY, KANSAS
 COMMENCED: 9-24-65
 COMPLETED: 10-3-65

0	29	Sand
29	660	Red Shale
660	1830	Lime, Shale
1830	2330	Shale, Shells
2330	3785	Shale, Lime
3785	3815	Lime
3815	3845	Lime, Chert
3845	3988	Lime
3988	4310	Lime, Shale
4310	4381	Mississippi
4381	4545	Lime
4545	4570	Lime, Chert
4570	4705	Lime, Shale
4705	4715	Sand
	<u>4715</u>	<u>RTD - D. & A.</u>

RECEIVED
 OCT 7 1965
 10-7-65
 CONVENTION STATE OF KANSAS

Set 8 5/8" used surface casing @ 216' with 150 sacks HA5 Posmix

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Keller #1 well, located C SW SW of Section 30, Township 31 South, Range 6 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 6th day of October, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967