

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 33 TWP. 31 RGE. 6 E/W
Location as in quarters or footage from lines:
N.W. N.W. S.W.

Locate Well
correctly on above
Section Platt.

Lease Owner Beren Corp.
Lease Name Wohlschlegal Well No. 1
Office Address Box 723/Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 04/05/81
Application for plugging filed 02/25/83
Plugging commenced 03/14/83
Plugging completed 04/18/83
Reason for abandonment of well or producing formation _____

Too much salt water

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ward

Producing formation _____ Depth to top _____ bottom _____ T.D. 4449

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	170	none
				5 1/2	4949	3195

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Sun Cementing pumped in:

30 cement Stop plug at 4500

Sand from 4500 to 4260

5 cement from 4260 to 4230

Ripped pipe at 3195

15 jell, 6 hull, 10 jell, 150 cement 3% c.c.

Morgenstern on location

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp. 5105

STATE OF Kansas COUNTY OF Barber, ss.

Elmer H. Morgenstern (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Elmer H. Morgenstern
(Address) Medford, Oregon

SUBSCRIBED AND SWORN TO before me this 28th day of April 19 83

Jessie Hamilton
STATE CORP. Notary Public

My Commission expires: April 4, 1986

MAY 02 1983
5-2-83
CONSERVATION DIVISION
Wichita, Kansas

15-077-00033-00-01

RILLERS LOG

WOHLSCHLEGAL #1
OWWO

Harper County
NW NW SW
Sec. 33-31S-6W

Company: Beren Corporation

Contractor: BEREDCO INC.

Comm: 4/2/81

Comp.: 4/5/81

Casing: 5 1/2", 14# set with 200 sacks pozmix @ 4949'

FORMATION FROM TO
No formations available (OWWO)

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1983
2-28-83
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF SEDGWICK

I certify that this is a true and correct copy of the above log as shown by the drilling reports.

BEREDCO

[Signature]

Subscribed and sworn to before me this 13th day of May, 1981.



[Signature]

TRANSIT CORP # WOHLSCHLEGAL 33-31-6W NW NW SW
Contr. TRANSIT CORP HARPER County
E. 1416 RR Comm Comp. 10-14-55 IP, D & TA

Tops	Depth	Datum
HEEB	3154	-1738
STAL	3170-	-1754
KC	3720	-2304
B/KC	3943	-2527
MISS	4313	-2897
KIND	4615	-3199
SIMP	4738	-3322
ARB	4886	-3470
TD	4936	-3520

Casing
8" 175

DST 4314-23/1 HR, GAS/20"
45' GSY MUD, BHP 1600#
DST 4327-65/1 HR, 200' GSY
MUD, BHP 1430#

