

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 35 Twp. 31S Rge. 6W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE SE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Clarahan Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 27, 1957

Application for plugging filed September 27, 1957

Application for plugging approved September 27, 1957

Plugging commenced September 27, 1957

Plugging completed September 27, 1957

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	9-8-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 250 feet.
Set plug at 250' & cemented with 20 sacks cement. Filled hole to 30'. Set plug at 30' with 1/2 sack hulls and cemented to base of cellar with 10 sacks.

10-9-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1957

Sanetta M. Duncan Notary Public.

My commission expires December 19, 1960

PLUGGING
NO. SEC 35 T 31 R 6W
BOOK PAGE 49 LINE 32

CLARAHAN #1

NE/4 SE/4 NE/4 of Section 35-31S-6W, Harper County, Kansas

Rigged up Rotary Tools 9/7/57

Ran 8 Jts. (248.56') 8 5/8 Surface Pipe
set @ 258'. Cemented w/175 sacks
cement, 2% CC

Tore down Rotary Tools 9/27/57

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0'	70'
Shale & shells	70	258
Shale, shells & redbed	258	810
Anhydrite & shale	810	1070
Lime	1070	1115
Lime & shale	1115	1445
Lime	1445	1730
Lime & shale	1730	2006
Shale w/lime streaks	2006	2216
Shale & lime	2216	2365
Shale w/lime shells	2365	2474
Shale w/lime	2474	2940
Shale w/lime streaks	2940	3035
Lime & shale	3035	3099
Sandy shale	3099	3226
Lime & shale	3226	3360
Sand & shale	3360	3451
Lime & shale	3451	3710
Lime	3710	3828
Lime & shale	3828	4147
Shale w/lime streaks	4147	4196
Lime & shale	4196	4243
Lime	4243	4320
Lime & shale	4320	4373
Lime	4373	4479
Lime & chert	4479	4543
Lime, chert & shale	4543	4595
Lime & shale	4595	4670
Simpson Sand	4670	4675
Sand	4675	4680 T. D.

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct,
to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 30th day of September, 1957

James Swancy
Notary Public

My Commission Expires: July 29, 1961

RECEIVED
OCT 9 1957
10-9-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 35 T 31 R 6W
BOOK PAGE 49 LINE 32