

LEASE NAME Schrock 'C'

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 31S RGE. 5 (E) or (W)

COUNTY Harper

Date Well Completed

Plugging Commenced 6-14-96

Plugging Completed 6-18-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Robinson Oil Company

ADDRESS 300 W. Douglas, Ste 420 Wichita, Ks. 67202

PHONE (316) 262-6734 OPERATORS LICENSE NO. 5038

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4578'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	263'	none
				4 1/2"	3719'	2882'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 3460' and 4 sacks cement. Shot well at 2882'. Pulled casing up to 900' pumped 35 sacks cement, pulled up to 525' pumped 35 sacks cement, pulled up to 300' circulated to surface with 100 sacks cement. Pulled rest of casing, topped off with 10 sacks cement. 60/40 poz 4% gel Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robinson Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 96

[Signature]
 Notary Public

My Commission Expires:

