

15-077-30154-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Harper County, Sec. 9 Twp. 31S Rge. 6W (E) (W)
Location as "NE/CNW&SW" or footage from lines C NE NW
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Bauer Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed January 5 19 66
Application for plugging filed April 13, 1970 19
Application for plugging approved April 14, 1970 19
Plugging commenced April 22, 1970 19
Plugging completed April 24, 1970 19
Reason for abandonment of well or producing formation Nonproductive of oil in commercial quantities.
If a producing well is abandoned, date of last production April 13, 1970 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Mississippi Depth to top 4322 Bottom 4734 Total Depth of Well 4747 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	FROM	TO	SIZE	PUT IN	PULLED OUT
			8 5/8"	225 ft.	Cemented
			5 1/2"	4740 ft.	3609 ft.

STATE RECEIVED
CORPORATION COMMISSION
MAY 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4747 ft. to 4700 ft. Five sacks cement from 4700 ft. to 4670. Set plug at 290 ft. Rock from 290 ft. to 280 ft. Ran 4 1/2 yards of ready mix cement to plug well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 156, Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Bldg., Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 5th day of May, 19 70

Evelyn Wanko
Notary Public.



15-077-30154-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BAUER #1
C NE NW SECTION 9-31S-6W
HARPER COUNTY, KANSAS

COMMENCED: NOVEMBER 28, 1965
COMPLETED: DECEMBER 14, 1965

OPERATOR - ALPINE OIL & ROYALTY Co., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	35	SAND	
35	225	RED BED AND SHALE	RAN 5 JOINTS OF 8-5/8" CASING, SET @ 225' w/215 SACKS CEMENT.
225	400	RED BED	
400	1190	SHALE	
1190	1385	LIME AND SHALE	
1385	1840	LIME	
1840	3170	LIME AND SHALE	
3170	3265	SHALE	
3265	3750	SANDY SHALE	
3750	3815	LIME AND SHALE	
3815	3986	LIME	
3986	4011	SHALE	
4011	4200	LIME	
4200	4335	LIME AND SHALE	
4335	4360	LIME	
4360	4500	CHERT AND LIME	
4500	4660	LIME	
4660	4715	LIME, SHALE AND SAND	
4715	4736	LIME	
4736	4740	LIME, SHALE AND SAND	
4740	4747	SAND	
4747	TD		RAN 147 JOINTS OF 5 1/2" CASING, SET @ 4740' w/175 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1970
5-6-70
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE NW SECTION 9-31S-6W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 15TH DAY OF DECEMBER, 1965, PERSONALLY APPEARED E. E. HALL; TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

BARBARA J. LAYTON
NOTARY PUBLIC
SEDGWICK CO., KANSAS
EXPIRES FEBRUARY 1, 1968.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC