15-077-20035-00-01


RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1975
1-7-75
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Harper County. Sec. 10 Twp. 31 Rge. 6W (E) (W)

Location as "NE/CNWSWS" or footage from lines C NW SW

Lease Owner Raymond Oil Co., Inc.

Lease Name Park #1 Well No.

Office Address Wichita, Kansas 67220

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 12/13/74 19

Plugging completed 12/20/74 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4384 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	251	none
				5½"	4382	3318'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4280' and sand bridged at 600'. Set 5 sacks cement at 4280'. Shot pipe at 3913', 3812', pulled 116 joints. Set rock bridge at 300' and ran 4 yards ready mix to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.

WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth

CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 74

Margaret Melcher
Notary Public.

My commission expires

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

15-077-20035-00-01

STENCILED

DEC 9 1967

KANSAS GEOLOGICAL SOCIETY

KANSAS WELL LOG BUREAU — KANSAS WELL SAMPLE BUREAU

KANSAS GEOLOGICAL SOCIETY BUILDING

508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

COMPANY FURSETH, HILL & DARNELL OIL


SEC. 10 T. 31 R. 6W

LOC C NW SW

FARM Park NO. 1

COUNTY Harper

KANSAS



TOTAL DEPTH 4384'

COMM. 9-22-67 COMP. 10-2-67

SHOT OR TREATED

CONTRACTOR Garvey Drilling

ISSUED 12-9-67

CASING

20	10	
15	8 5/8" 251'	cem w/ 200 sx
12	6	
13	5 ½" 4382'	cem w/ 100 sx

ELEVATION 1506' KB

PRODUCTION SIGW SITP 1400

Miss 4294-4328

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Rock, Surface Sand, and Shale	170
Red Bed and Shale	815
Shale and Lime	1430
Lime and Shale	1950
Shale and Lime	3585
Lime and Shale	3872
Lime	4123
Shale	4220
Shale with Lime	4309
Cherty Lime	4328
Chert	4343
Chert and Lime	4373
Chert	4384
RTD	4384

LOG TOPS

Heebner	3144
Shalnaker Sand	3440
Kansas City	3702
Mississippi	4282
Osage	4338

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
12-2-74
CONSERVATION DIVISION
Wichita, Kansas