

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Take All Information Completely
State Required Affidavit
Must be Delivered Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217

Harper County, Sec. 10 Twp. 31S Rgc. (X) 6 (W)

Location as "NE/CNW/SW" or footage from lines C SW SW
Graves Drilling Co., Inc.

Lease Owner: Graves Drilling Co., Inc. Well No. 1

Lease Name: Hostetler Office Address: 910 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 2 19 75

Application for plugging filed July 2 19 75

Application for plugging approved July 2 19 75

Plugging commenced July 2 19 75

Plugging completed July 2 19 75

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas

Producing formation Depth to top Bottom Total Depth of Well 439 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 180'. Followed by wooden plug and 1/2 sack hulls
Placed 25 sacks cement into hulls. Mudded up with heavy mud to 40 feet followed
by wooden plug, 1/2 sacks hulls and 10 sacks cement to base of well cellar.
Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1975
7-11-75
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor: (If additional description is necessary, use BACK of this sheet)
Graves Drilling Co., Inc.
Address: 910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF Sedgwick ss.
John C. Graves

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of July 19 75

My commission expires May 9, 1979 Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: June 22, 1975
 910 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 2, 1975
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 213' of 8 5/8" LOCATION: Hostetler No. 1
 cemented with 160 sacks SW SW
 Section 10-31S-6W
 Harper County, Kansas

0 - 215	Clay & shale
215 - 1035	Shale & shells
1035 - 1390	Shale, shells & lime streaks
1390 - 1598	Shale & lime
1598 - 1805	Lime
1805 - 2005	Lime, shale & sand
2005 - 2110	Shale & lime
2110 - 2470	Lime & shale
2470 - 2745	Lime, shale & sand streaks
2745 - 3170	Shale & lime
3170 - 3354	Lime, shale & sand streaks
3354 - 3595	Shale & lime
3595 - 3679	Shale
3679 - 3835	Lime
3835 - 4230	Lime & shale
4230 - 4267	Shale & lime
4267 - 4319	Chert
4319	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 11 1975
 7-11-75
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 10th day of July, 1975

Mr commission expires: May 9, 1979

Betty Brandt
Betty Brandt Notary Public