


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Harper County. Sec. 10 Twp. 31 Rge. 6W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW-SW

Lease Owner Graves Drilling Co.
Lease Name Hostetler (OWWO) Well No. 1
Office Address 910 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry

Date Well completed 10-19- 1976
Application for plugging filed 6- 8- 1976
Application for plugging approved 10-18- 1976
Plugging commenced 10-25- 1976
Plugging completed 11- 2- 1976

Reason for abandonment of well or producing formation
Dry

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstien
Producing formation Depth to top Bottom Total Depth of Well 4319'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	None
				4 1/2	4316	3986

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4316' to 4216'
4 sacks cement from 4216' to 4180'

Ripped at 3986' and pulled 4 1/2"

Wooden bridge at 360'
Rock from 360' to 350'
6 yards ready mix

RECEIVED
FEB 03 1977
2-3-77
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation, Box 187, Medicine Lodge, Kansas 67104

STATE OF Kansas COUNTY OF Barker, ss.
Elmer R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Morgenstern

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 77

My commission expires April 4, 1978

James Hamilton
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: June 22, 1975
910 Union Center
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 2, 1975
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 5 Jts. 213' of 8 5/8" LOCATION: Hostetler No. 1
cemented with 160 sacks SW SW
Section 10-31S-6W
Harper County, Kansas

0 - 215 Clay & shale
215 - 1035 Shale & shells
1035 - 1390 Shale, shells & lime streaks
1390 - 1598 Shale & lime
1598 - 1805 Lime
1805 - 2005 Lime, shale & sand
2005 - 2110 Shale & lime
2110 - 2470 Lime & shale
2470 - 2745 Lime, shale & sand streaks
2745 - 3170 Shale & lime
3170 - 3354 Lime, shale & sand streaks
3354 - 3595 Shale & lime
3595 - 3679 Shale
3679 - 3835 Lime
3835 - 4230 Lime & shale
4230 - 4267 Shale & lime
4267 - 4319 Chert
4319 Rotary Total Depth

RECEIVED
STATE GEOLOGICAL COMMISSION
JUN 08 1976
6-8-76
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves
President

STATE OF KANSAS)
SEDGWICK COUNTY) SS

Subscribed and sworn to before me, a Notary Public, this 10th day of July, 1975

My commission expires: May 9, 1979

Betty Brandt
Betty Brandt Notary Public

Copy to Population Commission
Copy to Sedgwick County
Copy to Kansas Geological Survey