

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-077-20,947-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003 *6-83*
(owner/company name) (operator's)

ADDRESS 110 South Main Suite 500 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9697

LEASE Burgess "B" WELL# 3 SEC. 20 T. 31S R. 8W (East/West)

- NW - SE - SE SPOT LOCATION/QQQQ COUNTY Harper

990' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 254' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4393' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open Hole 4393-4403'

ELEVATION 1579 1589 ^{RTD} T.D. 4403' PBD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand to 4350' & cap with 4 sacks cement or set CIBP @ 4350'

& cap with 2 sacks cement. Shoot pipe according to stretch. Pull pipe to 1350' & spot 30 sacks cement. Pull pipe to 900' & spot 30 sacks cement. Pull pipe to 310' & circulate cement to surface. Pull remaining casing & top off cement. 60/40 Poz 2% Gel (S. VanGieson)
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS

Daryl Hanson PHONE# (316) 532-5292 *MAR 30 1993*

ADDRESS Kingman, KS City/State _____

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 50846 *3-30-93*
(company name) (contractor's)

ADDRESS P. O. Box 781624, Wichita, KS 67278 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: _____ AUTHORIZED OPERATOR/AGENT: _____
[Signature]
(signature)

2)

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 30, 1993

McCoy Petroleum Corp
110 S Main 500
Wichita KS 67202

Burgess B 3
API 15-077-20,947-0000
990'FSL-990'FEL
Sec. 20-31-08W
Harper County

Dear Mr. Roger McCoy,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809