

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, Kansas

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Gas  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lan.-KC Depth to top 3283 bottom 3512 T.D. 3571

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lan.-KC	Gas	3283	3512	4 1/2	3564'	-----
	Fresh Water	-0-	200	8 5/8	225	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped down 4 1/2" casing - 1 sx. hulls, 40 sx. cement 60/40 Poz., 6% gel., 13 sx. gel., and 90 sx. cement 60/40 Poz., 60% gel. - cement. 3290' to 2690', gel. 2690' to 1350'. Cement from 1350' to surface. Pressured to 1000# on 4 1/2" SI hooked to 8 5/8" and pressured up immediately to 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
 Address Russell, Kansas

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Terry W. Piesher (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesher  
 (Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of May, 1989  
Marcia Yost  
 NOTARY PUBLIC  
 My Commission expires 10-28-91