

API NUMBER 15-165-21,659-0000

LEASE NAME Legleiter

WELL NUMBER 1

4080 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 8 TWP. 17SRGE. 19 (E164(W))

COUNTY Rush

Date Well Completed 7/28/94

Plugging Commenced 7/28/94

Plugging Completed 7/28/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DECAB Company

ADDRESS P. O. Box 609, Hays, Kansas 67601

PHONE#(913) -625-4086 OPERATORS LICENSE NO. 30347

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/28/94 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	244'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3900'-1350' 10 sks cement @ 40'

50 sks cement @ 1350' 15 sks in rathole

80 sks cement @ 650' 10 sks in mousehole

50 sks cement @ 250'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DECAB Company

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) Kyle B. Branum

Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 94

[Signature]
Glenda R. Tiffin, Notary Public



15.165-21659-0000

EMPHASIS OIL OPERATIONS
A Division of N-B Company, Inc.
P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: DECAB Company
P. O. Box 609
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Legleiter WELL #1

LOCATION: Approx. SW NW NE
Section 8-17S-19W
Rush County, Kansas

ROTARY TOTAL DEPTH: 3900'

ELEVATION: 2106' K.B.

COMMENCED: 7/22/94

COMPLETED: 7/28/94

CASING: 8-5/8" @ 244' w/130 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	440'	Shale & Lime	2135'
Shale	600'	Lime & Shale	2436'
Cedar Hills	715'	Shale & Lime	3450'
Shale	1000'	Lime & Shale	3528'
Anhydrite	1315'	Lime	3785'
Shale	1348'	Conglomerate	3876'
Lime & Shale	1768'	R.T.D.	3900'

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.




Kyle B. Branum

Subscribed and sworn to before me on July 28, 1994.

My commission expires: February 6, 1996.





Glenda R. Tiffin, Notary Public

AUG 01 1994
CONSERVATION DIVISION