


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County, Sec. 8 Twp. 17S Rge. 19 ~~EW~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
S/2 SE SW
Lease Owner D N B Drilling, Inc.
Lease Name DeWald 'A' Well No. 1
Office Address 515 R.H. Garvey Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Date Well completed 3-4 1979
Application for plugging filed 3-4 1979
Application for plugging approved 3-4 1979
Plugging commenced 3-4 1979
Plugging completed 3-4 1979
Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered
If a producing well is abandoned, date of last production
-- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3987
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	221'	8-5/8"	214'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 500', plug, 50 sx
Fluid to 210', plug, 25 sx
Fluid to 40', plug, 10 sx

RECEIVED
STATE CORPORATION COMMISSION
3-9-79
MAR 9 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor DNB DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
515 R.H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 79

My commission expires April 30, 1979
Dorothy L. Schmidt
Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLER'S LOG

D N B DRILLING, INC.
No. 1 DeWald 'A'
S/2 SE SW Sec. 8-17S-19W
Rush Co., Ks.

Commenced: 2-24-79
Completed: 3-4-79

Surface Casing: 214' of 8-5/8"
cmtd w/150 sx common, 2% gel,
3% cc

FORMATION

DEPTH

Surface Hole	0 - 221
Shale & Sand	221 - 1220
Shale & Lime	1220 - 2175
Lime & Shale	2175 - 2320
Shale & Lime	2320 - 2650
Lime & Shale	2650 - 3525
Lime	3525 - 3685
Lime & Shale	3685 - 3904
Lime	3904 - 3987 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 5th day of March, 1979.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Appt. Exp. April 30, 1979

RECEIVED
MAR - 9 1979
3-9-79
CONSERVATION DIVISION
Wichita, Kansas