

15-165-01792-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rush County. Sec. 4 Twp. 18S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 SW 1/4

Lease Owner Solar Oil Company

Lease Name Crotinger Well No. 1

Office Address 1117 Union National Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-6, 19 58

Application for plugging filed 10-6, 19 58

Application for plugging approved 10-6, 19 58

Plugging commenced 10-6, 19 58

Plugging completed 10-6, 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1050'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 500'. Build solid bridge and cement with 20 sacks cement. Fill with heavy mud to 150' build solid bridge and cement with 20 sacks cement. Fill hole with heavy mud to 40'. Build solid bridge cement with 10 sacks cement. Cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 915 Union Center Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

William J. Duckett (employee of ~~owner~~ or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William J. Duckett

915 Union Center Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of October, 19 58

My commission expires August 20, 1960

A. R. Derrington  
Notary Public.  
STATE CORPORATION COMMISSION (A. R. Derrington)

PLUGGING  
FILE SEC 4 T. 18 R. 16W  
BOOK PAGE 135 LINE 30

OCT 22 1958  
10-22-58  
CONSERVATION DIVISION  
Wichita, Kansas


15-165-01792-0000  
WELL LOG

COMPANY Solar Oil Company  
FARM Crotinger NO. 1

SEC. 4 T. 18S R. 16W  
LOC. NE 1/4 SW 1/4

TOTAL DEPTH 3538'  
COMM. 9-24-58 COMP. 10-6-58  
SHOT OR TREATED  
CONTRACTOR Lewis Drilling Company  
ISSUED

COUNTY Rush  
KANSAS



CASING  
20 10  
15 R 8-5/8" - 1050'  
12 6  
13 5

ELEVATION 1987 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 40 Surface Soil & Clay  
40 - 100 Sand & Clay  
100 - 255 Shale  
255 - 445 Shale & Pyrite  
445 - 465 Sand Stone & Pyrite  
465 - 570 Dakota Sand  
570 - 595 Shale  
595 - 975 Shale & Red Beds  
975 - 1040 Red Bed  
1040 - 1075 Anhydrite  
1075 - 1280 Red Bed  
1280 - 1715 Red Bed & Shale  
1715 - 1995 Shale & Lime Streaks  
1995 - 2680 Shale & Lime  
2680 - 2820 Shale  
2820 - 3225 Shale & Lime  
3225 - 3534 Lime  
3534 - 3538 Granite  
3538 - Total Depth

Geologic Tops

Anhydrite 1040  
Topeka 2960  
Heebner 3198  
Lansing KC 3255  
Base of the KC 3483  
The Weathered Granite 3525  
Granite 3529

PLUGGING  
FILE SEC. 4 T. 18 R. 16W  
BOOK PAGE 135 LINE 30

RECORDED  
STATE OF KANSAS  
10-22-58  
OCT 22 1958

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Sedgwick ) SS:

I, William J. Duckett of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Crotinger #1 well.

William J. Duckett

Subscribed and sworn to before me this 9th day of October 19 58

My Commission Expires: August 20, 1960

A. R. Derrington  
NOTARY PUBLIC  
(A. R. Derrington)