

15-165-02082-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

NORTH

X			

Locate well correctly on above
Section Plat

RUSH County. Sec. 19 Twp. 18S Rge. 16 (E) (W)
 Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Cen. of SW/4 SW/4 SW/4
 Lease Owner L. H. Wentz (Oil Division)
 Lease Name John Rodie Well No. 1
 Office Address Box 111, Ponca City, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed October 21, 1947
 Application for plugging filed October 21, 1947
 Application for plugging approved October 21, 1947
 Plugging commenced October 21, 1947
 Plugging completed October 21, 1947
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
 Producing formation Dry Hole Depth to top Bottom Total Depth of Well 3670 Feet
 Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	410'	620'	12-3/4"OD	105'	None
Basal Sand	Dry	3643'	3663'	8-5/8"OD	860'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3670' to 800' - Heavy Rotary Mud (Wooden Plug from 800' to 799')
 " 799' to 719' - 25 sacks Raw Cement pumped by Halliburton through drill pipe
 " 719' to 329' - Heavy Rotary Mud
 " 329' to 216' - 35 Sacks Raw Cement pumped by Halliburton through drill pipe
 " 216' to 40' - Heavy Rotary Mud
 " 40' to 39' - Wooden plug
 " 39' to 8' - 10 Sacks Raw Cement dumped
 " 8' to Surface - Cellar



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to L. H. Wentz (Oil Division)
 Address Ponca City, Oklahoma

STATE OF OKLAHOMA, COUNTY OF K A Y, SS.
 W. W. Davis (employee of owner) or ~~representative~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. H. WENTZ (OIL DIVISION)
W. W. Davis

Ponca City, Oklahoma
 (Address)

SUBSCRIBED AND SWORN to before me this 24th day of October, 1947

My commission expires August 6, 1950

David M. Gifford
 Notary Public.

PLUGGING
 FILE SEC 19 T 18 R 16 W
 BOOK PAGE 142 LINE 25

DRILLER'S LOG

Company: L. H. Wentz

Sec. 19, Twp. 18S, Rge. 16W
SW/4 SW/4 SW/4

Farm: John Rodie Well No. 1

County: Rush, Kansas

Total Depth: 3670'

Comm: 10-6-47; Comp: 10-21-47

Contractor: Glenn Peel Drilling Co., Inc.

CASING:12-3/4" 112' Cem.
8-5/8" 858' Cem.Elevation 1996'
Production: Dry.

Figures indicate Bottom of Formations

Surface Rock & shale	70
Shale & shells	112
Red bed, shale & shells	400
Sand & shale	515
Shale & shells	890
Red bed, shale & shells	1043 $\frac{1}{2}$
Anhydrite	1085
Shale & shells	1520
Salt & shale	1690
Shale & shells	1800
Lime & shale	1875
Anhydrite & lime	1980
Lime	2000
Lime & shale	2120
Lime	2265
Lime & shale	2505
Shale w/lime streaks	2705
Shale	2815
Shale & lime	2900
Lime	2955
Lime & shale	3050
Lime	3145
Lime w/strks. brown shale	3215
Lime & shale	3360
Lime	3610
Shale & lime	3630
Lime	3643
Basal Sand	3663
Weathered Granite	3668
Granite	3670
Total Depth	3670

Geological Tops:

Kansas City	3315 - 3373
Basal Sand	3643
Weathered Granite	3663
Solid Granite	3668

No shows.

This is to certify that the above information is, to the best of our knowledge, true and correct.

L. H. WENTZ (OIL DIVISION)

By: W. W. Davis
W. W. Davis

Subscribed and sworn to before me this 24th day of October, 1947.

10-25-47

OCT 25 1947

Charles M. Blufford
Notary PublicMy commission expires August 6 1949