

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 077 19024-0900 this well)

Operator's Full Name Texas Co. Inc.
Complete Address Box 2420 Tulsa, Okla. 74102
Lease Name Quinnmed Unit Tract 1 Well No. 4
Location SW-NE-SW- Sec. 24 Twp. 31^S Rge. 6 (E) (W) 4
County Harper Total Depth 4685
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling
Address Box 373 Geneseo, Kans. 67444 License No. 711
Operation Completed: Hour 2:30 pm Day 23 Month 9 Year 1978

The above well was plugged as follows:

512'-8⁵/₈" Casing w/ 400 sack Cement - 5 1/2" Casing set @
3700' w/ 150 sack Cement. Plug back to 3666' Top perf. 3400'
Howco mixed & pump 100 sack Cement in 5 1/2" Casing
through tubing to 3323' of Howco Cement retained. Shut in
w/ 800# pressure. Pull 2757' 5 1/2" Casing - Set bridge
@ 500' - Dump & yard ready mix Cement in 8 5/8" Casing
to top of Casing -
Harper Ready Mix, Harper, Ks. 67058

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature]
Well Plugging Supervisor

DATE 9.29.78 SEP 26 1978

INV. NO. 8179
CONSERVATION DIVISION
Wichita, Kansas