


 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed November 30, 1967.


DEC 18 1967
12-18-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Beardmore Drilling Company

Complete Address: 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Troyer Well No. # 1

Location C NW SE Sec. 14 Twp. 31 Rge. 8 (E) (W)

County Harper Total Depth 4840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour 2:00PM Day 12th Month December Year 1967

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was
filled with mud to 200', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 200', and cemented with 23 sacks,
with cement from 190' to 115'. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls
on fluid at 40', and cemented with 9 sacks, with cement from 30' to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Annie Elving
Well Plugging Supervisor

INVOICED

DATE 12/18/67

INV. NO. 6924-U