

15-677-30083-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Drlg. Co. Inc.

Complete Address 800 Bitting Bldg. Wichita, Ks

Lease Name Campbell SWD Well No. 1

Location C NE/SE Sec. 8 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 5226

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 10:00 AM Day 4 Month 10 Year 1971

The above well was plugged as follows:

230 ft 8 5/8 surface pipe cemented with 200 sacks. 4870 ft 5 1/2 long
string cemented with 150 sacks. Open hole. Sand back to 4850 ft,
5 sacks cement with bailer. Pulled 3640 ft 5 1/2. Set 10 ft rock
bridge at 220 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 10/5/71
INV. NO. 4407-4

Signed: A. Russell Bihart
Well Plugging Supervisor