

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1965

10-5-65

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Turley Oil Company

Complete Address: 117 North Broadway, Oklahoma City, Oklahoma

Lease Name Keller Well No. # 1

Location C SW SW Sec. 30 Twp. 31 Rge. 6 (E) (W)W

County	Harper	Total Depth	4715'
--------	--------	-------------	-------

Abandoned Oil Well	Gas Well	Input Well	SWD Well	D & A	X
--------------------	----------	------------	----------	-------	---

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 8:30 PM Day 3rd Month Oct. Year 1965

The Above well was plugged as follows:

216' of 8 5/8" surface pipe, cement circulated with 150 sacks. Hole was filled with drilling mud to 215', 1st cementing plug, bridged solid with dry cement and hulls on fluid at 215', and cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed:

Well Plugging Supervisor

INVOICED

DATE 10/5/65

INV. NO. 1916-41