

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1965
2-15-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name A. C. Gish Well No. # 4

Location NE NW NW Sec. 20 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4770'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 10:00AM Day 12th Month Feb. Year 1965

The Above well was plugged as follows:

629' of 8 5/8" surface pipe, cemented with 300 sacks. 4770' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 4387'. Top perforation
4378'. Bottom of the hole was sanded to 4360', and cemented with 5 sacks.
3710' of 5 1/2" long string was recovered from the hole. Fluid level in the
was now at 310', bridge plug was set on fluid at 310', and 10' of rock
bridge, and cemented with 25 sacks. Hole was filled with mud to 40',
and 10' of rock bridge, and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/15/65

INV. NO. 686-W