

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

APR 27 1964
4-27-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name A. C. Gish Well No. # 9

Location SW NW NW Sec. 20 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4772

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 2:00PM Day 24th Month April Year 1964

The Above well was plugged as follows:

638' of 8 5/8" surface pipe, cemented with 638 sacks. 4772' of 5 1/2" long
string, cemented with 225 sacks. Plug back to 4377'. Top perferation
4359'. Bottom of hole was sanded to 4350', and cemented with 10 sacks.
Fluid in hole was bailed down to 300'. Plug was set at 300', with 10'
of rock bridge, and cemented with 25 sacks. Hole was filled with mud
to 40', with 10' of rock bridge, and cemented with 10 sacks to base
of cellar.

3450' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/28/64
INV. NO. 9049-W

Signed: Archie Elving
Well Plugging Supervisor