

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11-16-70
NOV 16 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petrolaum, Inc.

Complete Address Rt. 2 Great Bend, Ks

Lease Name Wohlschlegel Well No. 3

Location C NE/NE Sec. 9 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4725

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe & Supply Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 3:00 PM Day 13 Month 11 Year 1970

The above well was plugged as follows:

216 ft of 8 5/8 surface pipe cemented with 225 sacks. 4705 ft of 5 1/2
long string cemented with 200 sacks. Top perf. 4302-06. Sand back
to 4230 ft, 5 sacks cement with bailer. Pulled 3805 ft of 5 1/2. Set
10 ft rock bridge at 185 ft. Fill hole with 3 1/2 yds. of redimix to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: G. Russell Biberstein
Well Plugging Supervisor

DATE 11/16/70

INV. NO. 2857-W