

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1965
2-23-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Wohlschlegel Well No. # 1

Location C SE SE Sec. 9 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4731'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 3:15PM Day 20th Month Feb. Year 1965

The Above well was plugged as follows:

216' of 8 5/8" surface pipe, cement circulated with 185 sacks. 4430' of
5 1/2" long string, cemented with 100 sacks. Top perforation 4308'. Cast
iron bridge plug was set at 4290, above all perforations. 3820' of 5 1/2"
long string was recovered from the hole. Hole was filled with mud to 235',
and 10' of rock bridge, and cemented with 25 sacks, bringing the top of
the cement to 165' in the surface pipe. Hole was filled with mud to 40',
and 10' of rock bridge, and cemented with 10 sacks to the base of the
cellar.

I hereby certify that ~~the~~ **INVOICED** above well was plugged as herein stated.

DATE 2/24/65
INV. NO. 729-W

Signed: Archie Elving
Well Plugging Supervisor