

15-077-30084-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
9-14-70
SEP 14 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address Rt 2 Great Bend, Ks

Lease Name Wohlschlegel Well No. 2

Location NW/NE Sec. 9 Twp. 31S Rge. 6 (E) W

County Harper Total Depth 4753

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sante Fe Pipe & Supply Co. Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 3:30 PM Day 10 Month 9 Year 1970

The above well was plugged as follows:

216 ft of 8 5/8 surface pipe cemented with 225 sacks. 4750 ft of
5 1/2 long string cemented with 150 sacks. Top perf. 4352-54. Sand
back to 4340 ft, 5 sacks cement with bailer. Pulled 2758 ft of 5 1/2.
Set 10 ft rock bridge at 265 ft. Fill hole with 4 yds redimix to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. J. [Signature]
Well Plugging Supervisor

DATE 9-14-70

INV. NO. 2521-W