

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

WATER CONTROL DISTRICT
JUL 21 1978
7-21-78
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -077-70404000 (of this well)

Operator's Full Name Texas Oil & Gas Corp.
Complete Address 200 W. Douglas Suite 300 - Wichita, Kans. 67202
Lease Name Hohlschlegel Well No. 1
Location Opp. C-SE-SE Sec. 9 Twp 31 Rge. 6 (E) (W) X
County Harper Total Depth 4364
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____
Plugging Contractor Clarke Corp.
Address 107 W. Fowler Medicine Lodge St. - 67104 License No. 853
Operation Completed: Hour 3:15 pm Day 19 Month 7 Year 1978

The above well was plugged as follows:
230' - 8 5/8" casing w/ 250 sack cement - 4 1/2" casing set @ 4348'
w/ 50 sack cement - plug back to 4320' - Top of - 4298' - 4308'
sand back to 4188' - Top sand w/ 4 sack mixed cement w/
dump bailer Pull 3500' - 4 1/2" casing. Set 10' rock
bridge from 200' to 290' Dump 4-gal. ready mix
in 8 5/8" casing to 5' below G.S.
Harper Ready Mix - Harper, Kans - 67058

I hereby certify that the above well was plugged as herein stated
Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 7-25-78
INV. NO. 7722-W