

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 077-20314-00-01 (of this well)

Operator's Full Name Graves Drilling Co Inc
Complete Address 910 Union Center Wichita, KS
Lease Name Hostetler Well No. 1
Location SW/SW Sec. 10 Twp. 31 Rge. 6 (E) (W) W
County Harper Total Depth 4319
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Clarke Corporation
Address 107 W Fowler Medicine Lodge, KS License No. 583
Operation Completed: Hour 11:00 AM Day 2 Month 11 Year 1976

The above well was plugged as follows:

203 ft 8 5/8 surface cemented with 150 sacks. 4316 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4275 ft. Sand to 4170 ft, 4 sacks
cerent with bailer. Pulled 4000 ft 4 1/2. Set 10 ft rock bridge at
360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *M Russell Bickerton*
Well Plugging Supervisor

INVOICED

DATE 11-4-76

INV. NO. 4098-W