

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued March 22, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1967  
4-24-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name S. O. Bishop Well No. # 3

Location NE SE NE Sec. 19 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4806'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 1:30PM Day 21st Month April Year 1967

The Above well was plugged as follows:

598' of 8 5/8" surface pipe, cement circulated. 4806' of 5 1/2" long string,  
cemented with 150 sacks. Plug back T.D. 4376'. Top perforation 4369'.  
Bottom of the hole was sanded to 4350', and cemented with 5 sacks, through  
the dump bailer. 3657' of 5 1/2" long string was recovered from the hole.  
Fluid level in the hole was at 350', bridge plug and rock bridge from 350'  
to 340', and cemented with 25 sacks. Hole was filled with mud to 40', rock  
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/24/67

INV. NO. 5107-W