

15-077-10034-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 22, 1967.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1967
4-17-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name S. O. Bishop Well No. # 2

Location SW NE NE Sec. 19 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4769'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 12:00PM Day 14th Month April Year 1967

The Above well was plugged as follows:

594' of 8 5/8" surface pipe, cemented with 325 sacks, 4769' of 5 1/2" long
string, cemented with 150 sacks. Plug back T.D. 4738'. Top perforation
4721'. Bottom of the hole was sanded to 4700', and cemented with 5 sacks,
through the dump bailer. 3415' of 5 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 300', bridge plug and rock bridge
from 300' to 290', and cemented with 25 sacks, from 290' to 215'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10
sacks, from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 4/17/67
INV. NO. 5058-W