

15-077-10033-0000

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1965

6-21-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name S. O. Bishop Well No. # 1

Location NE NE NE Sec. 19 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4780'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00 PM Day 18th Month June Year 1965

The Above well was plugged as follows:

623' of 8 5/8" surface pipe, cemented with 325 sacks. 4780' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 3945'. Top perferation
3926'. Bottom of the hole was sanded to 3900', and cemented with 5 sacks.
3800' of 5 1/2" long string was recovered from the hole. Hole was filled
with mud to 300', and 10' of rock bridged, and cemented with 25 sacks.
Hole was filled with mud to 40', and 10' of rock bridge, and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/22/65

INV. NO. 1344-W