

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1964

6-19-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. T. R. Sullivan of Sierra Petroleum Co., Inc has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Co. & Amerada Petroleum Corp.

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Browning Well No. # 1

Location: C SW SE Sec. 13 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4824 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

198' of 8 5/8" surface pipe, cemented with 165 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent