

State of Kansas



WM. H. AVERY Governor  
WILLIAM I. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC 18 1967

12-18-67

RECEIVED  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed November 30, 1967.

Dear Sir:

Mr. Emmet Hall of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name: Troyer Well No. # 1

Location: C NW SE Sec. 14 Twp. 31 Rge. 8 (E)(W) W

County Harper Total Depth 4840' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Hall was instructed to plug the well as follows:

212' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill  
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent