

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 5 - 1974
45-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gallagher of Gabbert & Jones Inc has this
date requested permission to plug the following described well:

Mr. Gallagher guarantees payment of the plugging fee.

Operator's full Name: Hollar Drilg Co Inc

Complete Address: 610 Petroleum Bldg Wichita, KS

Lease Name: Stevens A M.L. Well No. 1

Location: C NW/NE Sec 10 Twp. 31s Rge. 6 (E)(W) W

County: Harper Total Depth 3105 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gallagher was instructed to plug the well as follows:

217 ft 8 5/8 surface cemented with 175 sacks. Pump plug,

40 sacks cement to 200 ft. Mud to 40 ft, plug, 1 sack

hulls, 15 sacks cement to surface. 2 sacks cement in rat

hole.

Pumped by Allied Cementing Co. Great Bend, KS

Very truly yours,

[Signature]
Conservation Division Agent