

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES D. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED

JUN 9 1967

1-9-67

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Dale Robinson of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Robinson guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Ratzlaff "A" Well No. # 1

Location: C NW SE Sec. 1 Twp. 31 Rge. 7 (E)(W) W

County Harper Total Depth 4346' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Robinson was instructed to plug the well as follows:

216' of 8 5/8" surface pipe, cement circulated with 170 sacks. Fill hole with drilling mud to 215', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving  
Conservation Division Agent