

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1965
5-3-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Earl Baker of National Coop., Ref., Ass. has this date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: 1417 Wichita Plaza, Wichita, Kansas

Lease Name: Joslin Well No. # 1

Location: C NE NW Sec. 1 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4745 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Baker was instructed to plug the well as follows:

236' of 8 5/8" surface pipe, cement circulated with 190 sacks.
Fill hole with drilling mud to 225', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,
Archie Elving