

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

STATE CORPORATION COMMISSION

DEC 26 1962

12-26-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dec. 17, 1962.

Dear Sir:

Mr. Joe Cain of Jones-Gebert Oil Inc. has this date requested permission to plug the following described well:

Mr. Joe Cain guarantees payment of the plugging fee.

Operator's full Name: Jones-Gebert Oil Inc.

Complete Address: 1007 Central Bldg. Wichita, Kansas

Lease Name: Hibbard #1 Well No. #1

Location: C-NE-SE Sec. 1 Twp. 31 Rge. 7 (E) (W) X

County Harper County Total Depth 4734' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Joe Cain was instructed to plug the well as follows:

218' of 8 5/8" surface pipe with 175 sacks cement. Hole filled to 180' with heavy drill mud, 1/2 sack hulls, 1st cementing plug and 20 sacks cement. Hole filled to 40' with heavy drill mud 1/2 sack hulls, 2nd cementing plug and 10 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herman J. Gustus
Conservation Division Agent