

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1965
5-3-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address: 1417 Wichita Plaza, Wichita, Kansas

Lease Name Joslin Well No. # 1

Location C NE NW Sec. 1 Twp. 31 Rge. 7 (E) (W)W

County Harper Total Depth 4745'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 2:30 PM Day 29th Month April Year 1965

The Above well was plugged as follows:

236' of 8 5/8" surface pipe, cement circulated with 190 sacks. Hole
was filled with drilling mud to 225', 1st cementing plug, bridged
solid with hulls on fluid at 225, and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 5/3/65

INV. NO. 1084-W

Signed: Archie Elving
Well Plugging Supervisor

INVOICED