

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Koch Oil Corporation
 Complete Address: 321 W. Douglas, Wichita, Kansas
 Lease Name Beav Well No. 2
 Location Ch/2 SW NE Sec. 20 Twp. 31 Rge. 8W (W)
 County Harper Total Depth 4413
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated: _____
 Plugging Contractor: Knight Casing Pulling Co.
 Address: Chase, Kansas License No. 14
 Operation Completed: Hour _____ Day 15 Month 8 Year 60

The Above well was plugged as follows:

Checked hole to 4410'. Sanded hole to 4390' and
dumped 5 sq of cement w/ dump bailer. Pulled
5 1/2" casing. Pushed plug to 200 feet, set 10'
rock bridge to 190 feet. Ran 3 sacks of cement.
Bailed hole to 190 feet, ran 17 sacks of cement
and mudded hole to 40 feet, set 10 foot rock
bridge to 30 feet and ran 10 sacks of cement
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Fred W Hampel
 Well Plugging Supervisor
by S. S. Greider