

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 245 North Water
 Wichita, KS 67202

API Number 15 -165-20, 785 ⁰⁰⁰⁰ (of this well)

Operator's Full Name TENNECO OIL COMPANY
 Complete Address 3000 UNITED FOUNDERS BLVD.
 Lease Name PECHANE Well No. #1-24
 Location 1320 F.N.L - 1320 F.F.L Sec 24 Twp. 18 Rge. 17 (E) W
 County RUSH Total Depth 3660 ^{FT}
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor HAW DRILLING
 Address 1010 UNION CENTER BLDG - WICHITA, KS. License No.
 Operation Completed: Hour 3:15 PM Day 30th Month JUNE Year 1980

RECEIVED
 JUL - 9 - 80
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

The above well was plugged as follows: 1200ST COMMON 3% CA-CL.
8 5/8" 1060^{FT} SP. CLK. w/ 440ST 50/50 POZ MIX 6% GEL + 3% CA-CL
ORDERED 105ST 50/50 POZ MIX 6% GEL + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1ST PLUG @ 1050^{FT} w/ 60ST CMT.
2ND PLUG @ 390^{FT} w/ 30ST CMT.
3RD PLUG → SOLID BRIDGE HULL'S PLUG @ 40^{FT} TO 0 w/ 10ST CMT
5ST IN RAT HOLE

CEMENTED BY ALLIED CMT

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-10-80

INV. NO. 2560-W

Signed: Marion Schubert
 Well Plugging Supervisor