

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 12 1967

11-13-67

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Glenn N. Rupe

Complete Address: 222 Brown Bldg. Wichita, Kansas

Lease Name: Foos Well No. 1

Location: NE NE NW Sec. 34 Twp. 17 Rge. 19 (E)(W) X

County: Rush Total Depth 3941 Oil Well 1032

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gustus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace  
 100 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and  
 displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
 plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
 with 2 sc cement.

Very truly yours,

Leo F. Massey  
 Conservation Division Agent