

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1972

CONSERVATION DIVISION  
Wichita, KansasVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Rife Well No. E-1

Location: CNE-NW Sec. 22 Twp. 17 Rge. (E)(W) 19

County: Rush Total Depth 4015' Oil Well \_\_\_\_\_

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Burton was instructed to plug the well as follows:

258'--8 5/8" Surface casing, cement circulated with 140 Sx.

Circulate hole with heavy mud. Pull DP to 550' and displace 110 Cu. Ft.

cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP.

Pull DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Cu. Ft. cement to

bottom of cellar.

Very truly yours,

Conservation Division Agent